BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE

Office of the Executive Engineer Dasarahalli Division,

SCHDULE-B

Name of Work: Construction of Primary School Building in Dasarahalli Old Village Ward No.15 T.Dasarahalli Sub-Division.

Sl. No	Description of work	Unit	Qty	Sanctioned Rates	
				In Figures	In Words (Rs.)
1	2	3	4	5	6
1	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T& P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres complete as per specifications.C. Prestressed / Reinforced Cement Concrete Grade M-20 & above. complete as per specifications.	Cum	28.09	725.04	Rupees Seven Hundred Twenty Five and Four Paise Only
2	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T& P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres complete as per specifications.	Cum	28.81	180.20	Rupees One Hundred Eighty and Twenty Paise Only
3	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T& P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres complete as per specifications i) Lime/Cement Concrete. I. By Manual Means; B. Cement Concrete Grade M-15 and M-20. complete as per specifications.	Cum	33.06	271.36	Rupees Two Hundred Seventy One and Thirty Six Paise Only
4	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including T& P and scaffolding wherever necessary, sorting the dismantled material, disposal of unserviceable material and stacking the serviceable material with all lifts and lead of 1000 metres complete as per specifications. B.Rubble Stone masonry in cement mortar. MORTH Specification.	Cum	19.73	180.20	Rupees One Hundred Eighty and Twenty Paise Only
5	Loading and unloading of stone Boulder/stone aggregates /Sand/ Kanker/Moorum.KSRRB M100-1: Placing tipper at loading point, loading with front end loader, dumping, turning for return trip, Excluding time for haulage and return trip complete as per Specifications.	Cum	89.97	79.71	Rupees Seventy Nine and Seventy One Paise Only

Technical Manager (West)
KRIDL BBMP Bangalore

Signature of the Contractor

Executive Engineer

6	Earthwork excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead up to 50 m. after breaking of clods complete as per specifications.	Cum	191.34	132.50	Rupees One Hundred Thirty Two and Fifty Paise Only
7	Filling in foundation with granite/trap broken metal 10mm. and down size, with approved sand including hand packing, ramming, watering, including cost of all materials and labour with lead upto 50m. And lift of 1.5 m. complete as per specifications.	Cum	28.84	1114.06	Rupees One Thousand One Hundred Fourteen and Six Paise Only
8	Providing and laying in position plain cement concrete of mix M10 with OPC cement @ 220kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @0.465cum machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	35.94	4053.44	Rupees Four Thousand Fifty Three and Forty Four Paise Only
9	Providing and laying in position reinforced cement concrete of M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459cum super plastisiser @3ltrs confirming to IS9103-1999 Reaffirmed-2008,machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase,lintels, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	36.13	5142.06	Rupees Five Thousand One Hundred Forty Two and Six Paise Only
10	Providing and constructing granite / trap / basalt size stone masonry in foundation in cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	58.72	2710.42	Rupees Two Thousand Seven Hundred Ten and Forty Two Paise Only
11	Providing and constructing granite / trap / basalt rubble stone masonry in Basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.	Cum	12.92	3164.10	Rupees Three Thousand One Hundred Sixty Four and Ten Paise Only
12	Filling available excavated earth (excluding rock) in sides of foundations up to plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with lead up to 50 m. and lift upto 1.5 m. including cost of all labour complete as per specifications.	Cum	191.34	89.04	Rupees Eighty Nine and Four Paise Only

Technical Manager (West)
Signature of the Contractor
K.R.I.D.L. B.B.M.P. Bangalore

Executive Engineer

13	Earthwork excavation (in deposited soil) and filling sides of foundation upto plinth in layers not exceeding 20 cms. in depth, compacting each deposited layer by ramming after watering with all lead and lift including cost of all labour complete as per specifications.	Cum	82.19	177.02	Rupees One Hundred Seventy Seven and Two Paise Only
14	Providing and laying in position reinforced cement concrete of mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.69cum and fine aggregates @ 0.46cum super plastisiser @3ltrs confirming to IS9103-1999 Reaffirmed-2008,, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for R.C.C. beams, columns of all sizes in foundation plinth and superstructure ground floor level for column, including cost of all materials, labour, HOM of machinery, curing, complete as per specification.				
a	Ground Floor;-	Cum	47.35	5142.06	Rupees Five Thousand One Hundred Forty Two and Six Paise Only
b	FIRST FLOOR	Cum	34.42	5195.06	Rupees Five Thousand One Hundred Ninety Five and Six Paise Only
c	Second Floor	Cum	17.57	5248.06	Rupees Five Thousand Two Hundred Forty Eight and Six Paise Only
15	Providing and laying in position reinforced cement concrete of mix M20 with OPC cement @24 kgs with 12mm and down size graded granite metal, coarse aggregates @ 0.5175cum and fine aggregates @ 0.345cum with superplastiser @0.225ltrs machine mixed, well compacted for plain chajja of 7.5 cms. Average thickness, upto ground floor lever, including cost of all materials, labour, HOM of machinery, curing, complete as per specification.				
a	G.F	Sqm	10.80	376.30	Rupees Three Hundred Seventy Six and Thirty
b	F.F	Sqm	13.50	379.48	Rupees Three Hundred Seventy Nine and Forty
16	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as suspended floors, roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifications.				
a	G.F.	Sqm	417.47	254.40	Rupees Two Hundred Fifty

Technical Manager (West)
K.R.I.D.L. B.B.M.P. Bangalore
Signature of the Contractor

Executive Engineer

b	F.F.	Sqm	513.23	254.40	Rupees Two Hundred Fifty Four and Forty Paise Only
17	Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.	q	149.02	7187.86	Rupees Seven Thousand One Hundred Eighty Seven and Eighty Six Paise Only
18	Providing and constructing burnt brick masonry with approved quality of **non-modular bricks** of standard size of class designation 50 with cement mortar 1:4 for basement and superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.				
a	G.F alround	Cum	43.76	5045.60	Rupees Five Thousand Forty Five and Sixty Paise Only
b	F.F	Cum	43.76	5072.10	Rupees Five Thousand Seventy Two and Ten Paise Only
c	S.F Toilet	Cum	50.99	5098.60	Rupees Five Thousand Ninety Eight and Sixty Paise Only
19	Providing and laying in position reinforced cement concrete of M15 with OPC cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @0.459cum machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, walls (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc., including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	13.34	4406.42	Rupees Four Thousand Four Hundred Six and Forty Two Paise Only
20	Providing Honne wood frames of doors, windows, clerestory windows, ventilators, and other frames, wrought, framed or assembled including making plaster groves (excluding cost of cement concrete and side clamps), but including cost of materials, labour, HOM of machineries complete as per specifications.	Cum	2.54	75699.90	Rupees Seventy Five Thousand Six Hundred Ninety Nine and Ninety Paise Only

Technical Manager (West)
Signature of the Contractor
KRIDL BBMP Bangalore

Executive Engineer

21	Providing and fixing in position fully panelled Honne wood shutters for doors, styles and rails of 35mm. thick with bottom and lock rails 180mm wide top rail and styles 100mm wide as per drawing and panels of 25mm thick including cost of materials, labour, HOM of machineries complete as per specifications.	Sqm	15.44	3279.64	Rupees Three Thousand Two Hundred Seventy Nine and Sixty Four Paise Only
22	Providing and fixing in position Hanne wood fully panelled shutters for windows with styles and rails of 25mm. thick, 75mm wide in two halves with panels of 20mm thick including cost of materials, labour charges, HOM of machineries complete as per specifications.	Sqm	43.20	2921.36	Rupees Two Thousand Nine Hundred Twenty One and Thirty Six Paise Only
23	Providing and fixing M.S. grill work for windows and ventilators weighing 21 kg/sqm using M.S. flats, or M.S. square rods, or combination of M.S. flats and square rods as per approved design, drawing including cutting steel sections and welding the same to required pattern with a coat of red lead primer, cost of materials, fixtures, labour and HOM of machinery complete as per specifications.	Kgs	907.20	92.22	Rupees Ninety Two and Twenty Two Paise Only
24	Providing 12mm thick cement plaster in single coat with cement mortar 1:4,to brick masonry including rounding off corners wherever reuired smooth rendering, : Providing and removing scaffolding, including cost of materials, labour. Curing complete as per specifications.				
a	a) G.F **outside wall**	Sqm	169.33	124.02	Rupees One Hundred Twenty Four and Two Paise Only
b	F.F.	Sqm	169.33	127.20	Rupees One Hundred Twenty Seven and Twenty Paise Only
c	S.F.	Sqm	316.23	130.38	Rupees One Hundred Thirty and Thirty Eight Paise Only
25	Providing 15mm thick cement plaster in single coat with cement mortar 1:6 to brick masonry including rounding off corners wherever required smooth rendering, Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.				
a	G.F inside	Sqm	175.11	121.90	Rupees One Hundred Twenty One and Ninety Paise Only
b	F.F.	Sqm	175.11	126.14	Rupees One Hundred Twenty Six and Fourteen Paise Only

Signature of the Contractor

Executive Engineer

c	S.F.	Sqm	306.57	128.26	Rupees One Hundred Twenty Eight and Twenty Six Paise Only
26	Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications.				
a	G.F Ceiling Plastring	Sqm	158.94	147.34	Rupees One Hundred Forty Seven and Thirty Four Paise Only
b	F.F.	Sqm	158.94	150.52	Rupees One Hundred Fifty and Fifty Two Paise Only
c	S.F. Staircase Room	Sqm	55.59	153.70	Rupees One Hundred Fifty Three and Seventy Paise Only
27	Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications.	Sqm	1030.26	16.75	Rupees Sixteen and Seventy Four Paise Only
28	Providing white washing to new wall surface in two coats with lime of approved quality; to give an even shade including cost materials, labour, for fixing complete as per specifications.				
a	G.F	Sqm	169.33	5.83	Rupees Five and Eighty Three Paise Only
b	F.F.	Sqm	169.33	6.89	Rupees Six and Eighty Nine Paise Only
c	S.F.	Sqm	316.23	7.95	Rupees Seven and Ninety Five Paise Only
29	Applying of distemper providing and applying one coat distemper primer of approved brand on wall surface after thoroughly brooming the surface to remove all dirt, dust , mortar, drops and other foreign matter including preparing the surface, even and sand paper smooth, cost of materials, labour, completer as per specifications.	Sqm	1030.26	19.08	Rupees Nineteen and Eight Paise Only

Technical Manager (West)
B.D.A. / B.B.M.P. Bangalore

Signature of the Contractor

Executive Engineer

30	Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after througly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications.	Sqm	1030.26	53.00	Rupees Fifty Three Only
31	Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to given an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	654.90	46.64	Rupees Forty Six and Sixty Four Paise Only
32	Applying priming coat over new wood surface and / or wood based surface with white lead paint priming including preparing the surface after thoroughly cleaning oil, grease, dirt, and foreign matter, sand papering and knotting ready mix paint including cost of materials, labour, complete as per specifications.	Sqm	105.80	26.50	Rupees Twenty Six and Fifty Paise Only
33	Providing and applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, cleaning the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications.	Sqm	105.80	75.26	Rupees Seventy Five and Twenty Six Paise Only
34	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85 cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	22.89	4053.44	Rupees Four Thousand Fifty Three and Forty Four Paise Only
35	Providing and fixing Special make glazed Vitrified tiles (Granomite finis) of approved make, quality and colour of sized 600x600x10mm thick fixed on existing flooring wit ha special roffe adhesive for flooring and skirting etc., complete including providing spears at required interval and removing stains etc. complete as per specifications				
a	Flooring G.F	Sqm	165.20	1190.38	Rupees One Thousand One Hundred Ninety and Thirty Eight Paise Only
b	F.F.	Sqm	165.20	1191.97	Rupees One Thousand One Hundred Ninety One and Ninety Seven Paise Only
36	Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	52.20	70.28	Rupees Seventy and Twenty Seven Paise Only

Technical Manager (West)
KRIDL BBMP Bangalore
Signature of the Contractor

Executive Engineer

37	Providing lath plaster with cement mortar 1:3 5cms thick with 6mm dia mild steel bars at 20 cms c to c both horizontally and vertically fixing chicken mesh for drop chajja, facia, backing to cup boards including cost of all materials, labour, providing and removing form work HOM of machineries, curing, complete as per specifications.	Sqm	51.76	817.26	Rupees Eight Hundred Seventeen and Twenty Six Paise Only
38	Providng wall black boards in CM 1:3 with two coats of black paint including finishing etc. complete as per specifications	Sqm	24.00	752.60	Rupees Seven Hundred Fifty Two and Sixty Paise Only
39	SOLID PVC DOOR FRAME Providing & fixing factory made PVC Door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet metered cut at corners & jointed 2 No.s of 150mm long brackets of 15x15mm M.S. Square tube of 19 gauge. The door frame to be fixed to the wall using M.S.Screws of 65/80mm size complete as per manufacturers specification & direction of Engineer-in-charge.	Sqm	6.30	332.84	Rupees Three Hundred Thirty Two and Eighty Four Paise Only
40	Providing and fixing factory made splendor of solid core single leaf rigid composite polymer laminated sal wood, door shutter of required thickness, manufactured out of solid core door conforming to IS 22.2(Part-1) 1991, laminated with 0.8mm thick polymer, termite, water resistant and fire retardant with superior gluing based on vacuum lamination technology and wit h various per moulded design on both faces conforming to IS 6307-1985, using adhesive conforming to IS 4835-1979 and door shutters tested in conformation to 4020-1994. The finish of shutter will be TEADK/OAK/CEDAR/ROSE WOOD/WALNUT, plain colours WHITE/VORY/BEIGE/LIGHT GREY. Excluding cost of fixtures and inclusive of supply of shutters to respective work spot. with door shutter 30mm thick	Sqm	6.30	3074.00	Rupees Three Thousand Seventy Four Only
41	Providing Ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications.	Sqm	121.95	775.92	Rupees Seven Hundred Seventy Five and Ninety Two Paise Only
42	Supplying water storage tanks made of virgin polymer (LLDPE) with two layers outer black or blue and inner white layer of approved quality and make, conforming to I.S.I./ISO/SSI specifications.	L	2000.00	6.10	Rupees Six and Nine Paise Only
43	Providing and fixing on wall surface 2.0kg/sq.cm H.D.P.E rain down water pipes 110mm outer dia approved make and brand with necessary specials like shoes bends and offsets fixed with iron clamps, walls plugs, screws, including cost of materials, labour, complete as per specifications.	Mtr	131.00	466.40	Rupees Four Hundred Sixty Six and Forty Paise Only
44	Providing and fixing white vitreous china clay, water closets Orissa pattern of size 580 x 440mm with integral type footrests, 100m S or P trap, (approved make) cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Pan	4.00	1569.86	Rupees One Thousand Five Hundred Sixty Nine and Eighty Six Paise Only

Technical Manager (West)
KRIDL BBMP Bangalore

Signature of the Contractor

Executive Engineer

45	Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification.	Each	19.00	147.34	Rupees One Hundred Forty Seven and Thirty Four Paise Only
46	Providing and fixing white vitreous china clay, flat back, lipped front urinal basin of 430x260x350mm with 5 liters PVC automatic flushing cistern C.I. /M.S. brackets, standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete painting of fitting and brackets cutting and making good the wall and floor wherever required including cost of materials, labour complete as per specifications.	Unit	12.00	2446.48	Rupees Two Thousand Four Hundred Forty Six and Forty Eight Paise Only
47	Providing and fixing white vitreous china clay, surgeon type wash basin of size 660x460mm with single 15mm C.P brass pillar taps with single elbow operated levelers, C.I. /M.S. brackets, 32mm C.P. brass waste of standard pattern, painting of fitting and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications.	Unit	2.00	3142.90	Rupees Three Thousand One Hundred Forty Two and Ninety Paise Only
48	Providing and fixing in position brass gate valve with C.I. wheel of approved quality (screwed end) 40mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications.	Each	2.00	1046.22	Rupees One Thousand Forty Six and Twenty Two Paise Only
49	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fitting including fixing the pipe clamp at 10.00 meter spacing. This includes jointing of pipe and fittings with one step CPVC solvent cement and testing of joints complete as per specifications	m	150.00	127.20	Rupees One Hundred Twenty Seven and Twenty Paise Only
50	Constructing brick masonry inspection chamber 600x600mm, and 450 depth, (clear inside dimension) for single pipeline, using table moulded non-modular bricks of class designation 50 in cement mortar 1:5, C.I. cover with frame (light duty) 600x600mm, internal dimensions, total weight of cover with frame to be not less than 38kg (weight of cover 23kg and weight of frame 15kg) R.C.C. top slab with cement concrete 1:2:4 mix 20mm and downsize granite metal, foundation concrete 1:5:10 with 40mm and downsize granite metal inside plastering 12mm thick with cement mortar 1:3, finish smooth with a floating coat of cement on walls and bed concrete complete as per standard design including cost of materials, labour charges, curing complete as per specifications.	No.s	3.00	7027.80	Rupees Seven Thousand Twenty Seven and Eighty Paise Only
51	Providing and laying in position Yelahanka tiles of size 125 x 250mm of approved quality and make, over a bed of cement mortar 1:3 an average thickness 25mm over weather proof course and pointed with cement mortar 1:3 mix with red oxide including curing cost of materials, labour complete as per specifications.	Sqm	57.55	622.22	Rupees Six Hundred Twenty Two and Twenty Two Paise Only

Technical Manager (W...
Signature of the Contractor
KRIDL BBMP Bangalore

Executive Engineer

52	Concealed Coduit system-Supplying..... mm dia....mm thick heavy guage PVC conduit pipe with suitable size bends, metal junction boxs, adhesive paste etc and running before concreting the slabs. The conduit should be tied to the reinforcement rods by using binding wire and unused ways of junction boxes and pipe ends should be covered using PVC and enclosures and run with 18 SWG GI fish wire wherever necessary.				
a	a)25 mm dia 2mm Thick	Mtr	240.00	41.00	Rupees Forty One Only
53	Groove cutting in the wall supplying...mm dia...mmm thick heavy guage PVC conduit pipe with bends, metal junction boxes, adhesive paste etc., and bracing U of J hooks and cement plastering upto the surface and brick level and run with 18 SWG GI fish wire run throughout the conduit wherever necessary.The end of the conduit should be terminated with pvc end bushes. complete as per specifications.				
a	a) 25 mm dia 2mm Thick	Mtr	90.00	53.00	Rupees Fifty Three Only
54	point wiring using copper wire with switch supplying and wiring adopting loop system in existing pvc conduit/casing caping using COPPER PVC insulated multi strand 2*1.55qmm copper wire with a6a mps flush type SP control switch shall be fixed on the exisiting plastic sheet/gang box,the other end of the wites shall be terminated with sufficient loose length in a wood/pvc round block. complete as per specifications				
a	a) short point upto 3mtr from tapping point to out let via switch	Each	8	175.00	Rupees One Hundred Seventy Five Only
b	b) medium point above 3 mtr upto 6mtr from tapping point to out let via switch	Each	8	260.00	Rupees Two Hundred Sixty Only
c	c)long point above 6mtr upto 10 mtr from tapping point to out let via switch	Each	18	368.00	Rupees Three Hundred Sixty Eight Only
55	Supplying and flush mounting teak wooden box without from plank, made of not less than 12mm thick wood, after due groove cutting, necessary masonary patchwork complete as per specifications	Each	10	80.00	Rupees Eighty Only
56	Wiring for lighting/power circuit using one of pvc insulated 110v grade multistrand copper conductor single core cable in open or consealed system of wiring. complete as per specifications				
a	a.)1.5 Sqmm	Per Mtr	200.00	15.00	Rupees Fifteen Only
b	b)2.5 Sqmm	Per Mtr	450.00	25.00	Rupees Twenty Five Only

Signature of the Contractor

Executive Engineer

57	Supplying 6A flush/ Projected type socket and a 6 amps flush/projected type SP switch either surface/flush mounting in a existing gang box or in a 4mm thick plastic sheet and fixing over a flush mounted wooden box and wiring using necessary capacity wires as required.				
a	a)6AMps 3/5Way	Each	6	105.00	Rupees One Hundred Five Only
58	Supplying 4 mm thick plastic sheet with necessary nitches for fixing switches etc and fixing on Existing wooden or metal box using N.F Screws.)	Sqcm	1200.00	0.22	Twenty Two Paise Only
59	Extra for supplying 4 mm thick white platic plate and covering for junction boxes or size ..mm conduit using necessary machine screw complete as per specifications				
a	a) 80 mm	No	12	7.25	Rupees Seven and Twenty Five Paise Only
60	Supplying and fixing miniature circult breakers on existing MCB disribution boards using necessary fixing materials and wiring complete as required. Make: STANDARD, INDO ASIAN, complete as per specifications				
a	A) 5-32 Amps SP	Each	1	195.00	Rupees One Hundred Ninety Five Only
61	Supplying and fixing PBBC brass/ Bakelite straight or slant batten holder and wiring, within 60W/230 Volts lamps. Make: Lisha, Anchor,cona,ELLE,GM complete as per specifications	No	20	60.00	Rupees Sixty Only
62	Supplying of LT UG cable having aluminium conductor PVC insulated, sheathed, galvanised, steel wire/steel tape armoured cable with PVC outer sheathing 1.1 KV class complete as per specifications	Rmtr.	60.00	125.00	Rupees One Hundred Twenty Five Only
63	Digging of trench of 0.6m deep x 0.50mtr wide refiling the trench to the required ground level and consolidating etc. complete as per specifications	Rmtr.	40.00	140.00	Rupees One Hundred Forty Only
64	Supplying, fixing, wiring,earth electrode for grounding conduits I.C. cutouts and other equipments on the meter board using 40mm dia 2.90 thick G1 pipe 2..5 mtr long buried in a pit... the pit should be filled with equal proprotion of salt and charcoal 150mm alround the pipe to complete depth. the connection from the pipe to the conduit etc.. is to be established through G1wire of size as oer ISI specification 7.3.3.of IS 732 using 12mm dia bolts, nuts, washers and checknuts etc, the pipe shall have 16 through holes of 122mm dia.	Each	1	1950.00	Rupees One Thousand Nine Hundred Fifty Only

Technical Manager (West)
D.L. B.B.M.P. Bangalore

Signature of the Contractor

Executive Engineer

65	supplying and fixing of class a(medium duty) G1 pipe of wall thick ness not less than 3.25 mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class.complete as per specifications	Rmtr	20	240.00	Rupees Two Hundred Forty Only
66	Labour charges for laying of 1.1KV clas UG cable when supplied agency in existing trench G1 pipe/ stoneware pipe /on wall /on pope as required. complete as per specifications				
b	a) 6Sqmm to 16 Sqmm	Rmtr.	60.00	8.00	Rupees Eight Only
67	Supplying and running of G1/Copper srrips for grounding commections, using necessary fixing materials as required.complete as per specifications				
b	a) 25 x 3mm	Per Mtr	24.00	121.00	Rupees One Hundred Twenty One Only
68	supplying and fixing L.T cast from pot heads sultable for 1.1KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts nuts and washers etc. complete as per specifications				
a	a. 16 Sqmm	Each	1	260.00	Rupees Two Hundred Sixty Only

Signature of the Contractor

Executive Engineer,
Dasarahalli Division,

K R I D L B B M P Bangalore